

JAIPUR DEVELOPMENT AUTHORITY, JAIPUR

No. JDA/ E.E/ (DP-I) /01/ 2016-17/D- 241

Dated :- 21-4-16

शुद्धि पत्र

NIB No. : JDA/EE-DP-I/01/2016-17

इस प्रकोष्ठ द्वारा जारी निविदा सूचना NIB No. : JDA/EE-(DP-I)/01/2016-17 "Construction of Drain at Sirsi road from Panchyawala to Jhadkhand Mod Zone-7 JDA, Jaipur " जिसकी ऑनलाईन बोली आमंत्रित तिथि 04.05. 2016 को साय: 6.00 बजे तक है। उक्त निविदा की Technical Bid एवं उसकी शर्तों में वर्णित शब्द POTENTIAL ASSESSMENT के स्थान पर POST QUALIFICATION पढ़ा जावे एवं Schedule of works/BOQ में अपूर्ण अंकित Item के Description को नीचे सारणी में वर्णित Corrected description के अनुसार पढ़ा जावे जो कि निम्नानुसार है:-

Sr. No.	Sr. No. Given in Schedule of works	Already given Description of item in schedule of works	Corrected description of item
1	2.00	Dismantling of Flexible Pavements Dismantling of Flexible Pavements and disposal	Dismantling of Flexible Pavements Dismantling of Flexible Pavements and disposal of dismantled materials upto a lead of 100 m, stacking serviceable and unserviceable materials separately as per MoRD Specification Clause 202
2	4.00	Earth work in excavation by mechanical means All kinds of soils	Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sum on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including taking out the excavated soil and depositing and refilling of jhiri with watering & ramming and disposal of surplus excavated soil as directed with in a lead of 50 meter. All kinds of soils
3	7.00	Providing and Laying Reinforced Cement Concret Providing and laying reinforced cement concrete	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in Single Row Providing and laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets Clause 1106.
4	8.00	Providing and Laying Reinforced Cement Concre Providing and laying reinforced cement concrete	Providing and Laying Reinforced Cement Concrete Pipe NP4 as per design in Single Row Providing and laying reinforced cement concrete pipe NP4 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets Clause 1106.
5	9.10	Providing and laying in position cement concrete including curing, compaction etc. complete in specified grade excluding the cost of centering and shuttering - All work up to plinth level.	Providing and laying in position cement concrete including curing, compaction etc. complete in specified grade excluding the cost of centering and shuttering - All work up to plinth level.
		2) M15 grade Nominal Mix 1: 2: 4 (1 cement : 2 coarse sand : 4 graded sto	2) M15 grade Nominal Mix 1: 2: 4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size).

		4) M10 grade Nominal Mix 1: 3: 6 (1 cement : 3 coarse sand : 6 graded sto	4) M10 grade Nominal Mix 1: 3: 6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20mm nominal size).
6	12.10	Providing and laying in position Ready mix concr All works upto floor V floor M20 grade Design Mix by using min 400 Kg of ce	Providing and laying in position Ready mix concrete manufactured in fully automatic Batching Plant and transported to site in transit mixer for having continuous agitated mixer, manufactured as per approved mix design of specified grade of RCC work including pumping of R.M.C. from transit mixer to site of laying , excluding the cost of centering, shuttering and reinforcement with all lead and lift including cost of admixtures in recommended portion as per IS 9103 to accelerate/ retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer in charge. All works upto floor V floor M20 grade Design Mix by using min 400 Kg of cement per cum of concrete
7	14.00	Dismantling Kerb Stones Dismantling Kerb Stones by manual means and	Dismantling Kerb Stones Dismantling Kerb Stones by manual means and disposal of dismantled material with all lifts and upto a lead of 1000 m as per MoRD Specification Clause 202.

निविदा की अन्य शर्तें पूर्वानुसार रहेगी जिन्हे वेबसाइट www.jaipurida.org, www.sppp.raj.nic.in तथा <http://eproc.rajasthan.gov.in> पर देखी जा सकती है।



अधिशायी अभियंता (ड्रेनेज प्रोजेक्ट- I)
जविप्रा, जयपुर

प्रतिलिपि:-

1. पी. आर. ओ., जविप्रा, जयपुर।
2. अतिरिक्त मुख्य अभियंता-II, जविप्रा, जयपुर।
3. सिस्टम एनालिस्ट, जविप्रा, जयपुर को इंटरनेट पर प्रकाशित करने हेतु प्रेषित है।



अधिशायी अभियंता (ड्रेनेज प्रोजेक्ट- I)
जविप्रा, जयपुर